



Heater Installation Service

Description

Installation of new natural gas, LP or upgraded heater to an existing circulation system.

Services Include

- Disconnect existing heater from existing plumbing, electrical and ventilation.
- Deliver new heater to jobsite and set in position.
- Connect circulation system plumbing from filter to heater
- Connect gas supply from adequate existing supply riser to new heater. Including union, drip and shut off valve.
- Connect electric from adequate existing circuitry at the equipment locations. Include switch and weatherproof switch box and enclosure.
- Connect heater to ventilation.
- Start up and test heater for proper working order.
- Instruct owner on usage of new heater.

Options

- Disposal of heater by Poolblu, (additional fees apply).

Notes

- Adequate unobstructed access to and from the location exists.
- Existing plumbing is of standard configuration, including manual external bypass if required.
- Adequate electrical circuitry exists at location for connection to new equipment (if required).
- Obstructed access to and from the equipment location, (landscaping, fencing, stairs, blocked by existing plumbing or equipment, etc.), may involve additional costs.
- Additional circulation system plumbing, venting, gas connection or electrical work is quoted on a per job basis.

Availability

- Available in all North and Central American markets.